



**EXTRAS MATERIAL LEMNOS**

DENUMIRE ELEMENT	ELEMENTE GEOMETRICE			Aria (mp)	Nr. Buc (buc)	VOLUM	
	b (m)	h (m)	L (m)			Pe buc (mc)	Total (mc)
0	1	2	3	4	5	6	7
CAPRIORI	0.08	0.14	8.2	0.0112	42	0.09184	3.857
<b>VOLUM TOTAL CAPRIORI (mc)</b>							<b>3.857</b>
COSOROABE	0.15	0.15	18.5	0.0225	2	0.41625	0.833
<b>VOLUM TOTAL COSOROABE (mc)</b>							<b>0.833</b>
PANE	0.14	0.14	18.5	0.0196	3	0.3626	1.0878
<b>VOLUM TOTAL PANE (mc)</b>							<b>1.088</b>
CLESTI	0.048	0.18	8	0.00864	14	0.06912	0.96768
<b>VOLUM TOTAL CLESTI (mc)</b>							<b>1.169</b>
POPI	0.14	0.14	1.4	0.0196	14	0.02744	0.384
<b>VOLUM TOTAL POPI (mc)</b>							<b>0.823</b>
GRINZI JUG	0.2	0.3	8.5	0.06	2	0.51	1.02
<b>VOLUM TOTAL TALPI (mc)</b>							<b>1.870</b>
CONTRAFISE	0.1	0.12	1.2	0.012	36	0.0144	0.518
<b>VOLUM TOTAL CONTRAFISE (mc)</b>							<b>0.518</b>
<b>VOLUM TOTAL MATERIAL LEMNOS (mc)</b>							<b>10.158</b>

Proiectant general: S.C. ARHITECTURA GRAFICA DESIGN SRL nr. inreg. reg.com. 333/10/01994 c.f. R5910783	denumire proiect: <b>RECONSTRUIRE OBIECTIV DE ARHITECTURA POPULARA SCOALA SECURICENI</b>	Pr. nr. 392-2016
Proiectant de specialitate: S.C. STRUCTURA SRL SUCEAVA nr. inreg. reg.com. 533291/1993 c.f. R3407522	beneficiar: <b>MUZEUL BUCOVINEI</b>	Faza: P.T.
Proiectat sing. RUSU C-tin.	Scara 1:50	Nr. plansa R07
Verificat ing. RADIANOV V.	2016	
Sef proiect arh. GORCEA C.		